Town of Amherst Schedule of Infiltration and Inflow (I&I) – Contribution Removal Values By Source and Fee Schedule

I&I Mitigation Method	Severity	I&I Credit (gpm)*	Availability
Manholes			
Surface Water Entering MH/Inflow Protector Installed Or Low Lying/Buried MH Raised		4	No
Frame, Frame to Cone, Cone to Barrel, or Barrel Joint leaks Frame, Cone, Barrel leaks (not along joints)	Severe Moderate	5 3	No No
	Slight	1	No
	Severe Moderate	2 1	No No
	Slight Severe	0.5 15	No No
Expose frame and cone in ditch (Exterior)	Moderate Slight	10 5	No No
Manhole replacement	Š	15	No
Cracks in the concrete or paved surface area surrounding a manhole with leaks in frame and core		5	No No No
Pipe Segments			
Joint infiltration or cracked pipe		1	No
Pipe broken		2	No
Cured in Place Piping (CIPP) or Pipe Replacement per 100 feet	6" pipe	7	No
	8" pipe	8	Yes (\$250/gpm)
	10" pipe	9	No
		10	No
	15" pipe 18" pipe	13 15	No No
	21" pipe	17	No
	24" pipe	18	No
Private Sources	-:		
	Missing	0.1	No
Property lawn vents and clean outs	Low Lying Vent	1	No
	Loose/Broken Riser	10	No
Downspout		5	No
Sump pump		1	No
Deficient residential lateral building foundation to connection at right of way	Case -specific, no general classification	8	By approval of Town Engineer
Leaking lateral at the connection to the main (main to right of way)		12	Yes (\$250/gpm)

^{*} Source Erie County Division of Sewerage Management, General Infiltration and Inflow (I&I) - Contribution

 $Removals\ by\ Source,\ with\ exception\ of\ leaking\ lateral\ at\ the\ connection\ to\ the\ main\ and\ deficient\ residential$

lateral building foundation to connection at right of way